BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 19

Name of Work:-Maintenance of BBMP office in ward No- 02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Rate in Words
1	Providing and fixing 4"x1/2" size of beach wood design skirting	rmt	30	260.00	Rupees Two Hundred Sixty Only
2	Providing and fixing ventilation blindes for windows	sqm	5	119.00	Rupees One Hundred Nineteen Only
3	Visitor Chairs with arms	Nos	20	3915.00	Rupees Three Thousand Nine Hundred Fifteen Only
4	High back chair	Nos	2	6886.00	Rupees Six Thousand Eight Hundred Eighty Six Only
5	Lifting of Submersible Pump set **(P,46/I.10.3.21 RDED SR (2002-03)**	No	2	850.00	Rupees Eight Hundred Fifty Only
6	Transportataion of pumping machineries **(P.46/I.103)RDED SR (2002-03)**	No	2	900.00	Rupees Nine Hundred Only
7	**A) Repairs to Motor:**Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6months. **RDED SR (2002-03)P NO.39/ I,NO.A)**				
	a) -Do - above 3HP upto 5HP	No	2	2500.00	Rupees Two Thousand Five Hundred Only
	b) -Do - above 5HP upto 10HP	No	2	3700.00	Rupees Three Thousand Seven Hundred Only
	(Above 5HP upto 10HP add Rs.120/- for every 1/2 HP)				Rupees Zero
8	Above 5HP Stator (with one year Gurantee) **P.No.40/Ino.C(2)RDED SR (2002-03)**	No	2	5050.00	Rupees Five Thousand Fifty Only
9	Above 5HP Rotor (with one year Gurantee) **P.No.40/I No.C(2)RDED SR (2002-03)**	No	2	4700.00	Rupees Four Thousand Seven Hundred Only
10	Upper Flange **P.No.40/I No.3 RDED SR (2002-03)**	No	2	350.00	Rupees Three Hundred Fifty Only
11	Lower Housing **P.No.40/I No.4 RDED SR (2002-03)**	No	2	650.00	Rupees Six Hundred Fifty Only
12	Lower Flange **P.No.40/I No.5 RDED SR (2002-03)**	No	2	350.00	Rupees Three Hundred Fifty Only
13	a) Carbon Housing **P.No.40/I No.7A RDED SR (2002-03)**	No	2	475.00	Rupees Four Hundred Seventy Five Only
14	b) Thrust bearing block assembly complete with Segment bearing pad **P.No.40/I No.7B RDED SR (2002-03)**	No	2	1150.00	Rupees One Thousand One Hundred Fifty Only
15	c) Tip Carbon /Ferrodo pading **P.No.40/I No.7C RDED SR (2002-03)**	No	2	150.00	Rupees One Hundred Fifty Only
16	Bearing (Gun metal)Centrifugal cast Aluminium Bronze, bearing bush **P.No.41/I No,9 RDED SR (2002-03)**	No	2	400.00	Rupees Four Hundred Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Rate in Words
17	Motor Base with pin **P.No. 41/ I No.11 RDED SR (2002-03)**	No	2	475.00	Rupees Four Hundred Seventy Five Only
18	Re-erection charges of pumping machineries including overhauling and painting **P.No.41/I No 13,RDED SR (2002-03)**	No	2	950.00	Rupees Nine Hundred Fifty Only
19	Labour Charge (overhauling Motor only) **P.No.41/ I No.15 RDED SR (2002-03)**	No	2	550.00	Rupees Five Hundred Fifty Only
20	C) Replacement of pump parts: The following main components of submersible pump sets requiring replacement Pump bowls **P.No.39 / I No B1 RDED SR (2002-03)**	No	2	700.00	Rupees Seven Hundred Only
21	Intermediate piece (I.P) with IP leaded bronze bush **P.No. 44/ I No.B2 RDED SR (2002-03)**	No	2	450.00	Rupees Four Hundred Fifty Only
22	Oil seal **P.No. 44/ I No.B3 RDED SR (2002-03)**	No	2	125.00	Rupees One Hundred Twenty Five Only
23	Oil seal steel bush **P.No. 39/ I No.B4 RDED SR (2002-03)**	No	2	150.00	Rupees One Hundred Fifty Only
24	Guide vane Pno 39/I No B5 RDED (2002-03)	No	2	175.00	Rupees One Hundred Seventy Five Only
25	Impeller (shell moulded with aluminium and Bonze) P No 39/ I no B6 RDED SR 2002-03	No	2	425.00	Rupees Four Hundred Twenty Five Only
26	a) Discharge outlet (D.O) Bearing D.O Steel Bush **P.No. 39/ I No.B7 RDED SR (2002-03)**	No	2	445.00	Rupees Four Hundred Forty Five Only
27	b)D.O Bearing **P.No. 39/ I No.B7 RDED SR (2002-03)**	No	2	285.00	Rupees Two Hundred Eighty Five Only
28	Steel bush (D.O) steel bush) **P.No. 39/ I No.B8 RDED SR (2002-03)**	No	2	150.00	Rupees One Hundred Fifty Only
29	Allen Screw **P.No. 40/ I No.9 RDED SR (2002-03)**	No	2	25.00	Rupees Twenty Five Only
30	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) **P.No. 40/ I No.10 RDED SR (2002-03)**	No	2	950.00	Rupees Nine Hundred Fifty Only
31	Pump key (Stainless steel) **P.No. 40/ I No.11 RDED SR (2002-03)**	No	2	125.00	Rupees One Hundred Twenty Five Only
32	Pump coupling (stainless steel) **P.No. 40/ I No.12RDED SR (2002-03)**	No	2	250.00	Rupees Two Hundred Fifty Only
33	Non - Return valve (NRV) assembly complete with rubber 'O' Ring **P.No. 40/ I No.13RDED SR (2002-03)**	No	2	1350.00	Rupees One Thousand Three Hundred Fifty Only
34	Cabble guard **P.No. 40/ I No.14RDED SR (2002-03)**	No	2	150.00	Rupees One Hundred Fifty Only
35	Strainer **P.No. 40/ I No.15RDED SR (2002-03)**	No	2	150.00	Rupees One Hundred Fifty Only
36	Providing and fixing 50 mm dia heavy duty coller **SE RDED Approved rate**	No	2	130.00	Rupees One Hundred Thirty Only
37	Door Locks XIII SL 391	Nos	5	400.00	Rupees Four Hundred Only
38	PVC flusing cisten 10 lts low level with fittings SSIV SL 688	Nos	15	600.00	Rupees Six Hundred Only
39	110mm dia asbestos cement pipe of approved make (PVC) XX SL 585	Mtrs	100	172.00	Rupees One Hundred Seventy Two Only
40	KSRB 13.11.1: Providing and placing on terrace. Polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity) Specification NO. KBS 13.22 Page No. 91/ Item No. 13.78 / PWD SR 2015-16	**Each**	2.00	8851.00	Rupees Eight Thousand Eight Hundred Fifty One Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Rate in Words
41	Providing Supplying and commissioning of 1 HP submersible Monoblock pump with starter 15mm cable with necessary GI fittings with suction & Delivery hose pipes including necessary fittings etc completed as per specifications.	Nos	2.00	10000.00	Rupees Ten Thousand Only
42	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2012-13	**cum**	2.00	188.00	Rupees One Hundred Eighty Eight Only
43	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2012-13	**Cum**	0.30	4900.00	Rupees Four Thousand Nine Hundred Only
6	Providing and supplying Computer with Printer and all necessaory accories	Nos	1	25000.00	Rupees Twenty Five Thousand Only
44	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2015-16	**Cum**	3.60	6295.00	Rupees Six Thousand Two Hundred Ninety Five Only
45	Providing and fixing steel gurders as per Indian Standard Rolled Steel Beams I.S 800-1964 page No 37 item No 7.9 SR 2012-13	**Rmt**	2089.47	91.60	Rupees Ninety One and Paise Sixty Only
	a) Providing and fixiing steel	**Rmt**	2.00	10000.00	Rupees Ten Thousand Only
40	KSRB: 7.5 Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & operations complete Including pulling hooks, 4nos handles wit hall fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m Specification NO. KBS 7.10 / 7.12 Page No. 36/ Item No. 7.5/ PWD SR 2015-16	**sqm**	6.00	2838.00	Rupees Two Thousand Eight Hundred Thirty Eight Only
	Supplying and fixing/replacing of 6/16/32 Amps electrical accessories on existing switch board. Group A				

	Description	Unit	Approved Qty	Rate Quoted by the Contractor	
				Rate	Rate in Words
4 50/34	h) 6 Amps Bell Buzzer	Each	10	117.00	Rupees One Hundred Seventeen Only
	a) 6Amps SP Switch	Each	10	35.00	Rupees Thirty Five Only
	c) 6Amps 3Way 5 Pin Socket	Each	10	53.00	Rupees Fifty Three Only
	j) 16 Amps 3 way 5 pin socket	Each	10	94.00	Rupees Ninety Four Only
	k) 16 Amps 3 pin Top	Each	10	51.00	Rupees Fifty One Only
	l) 32 Amps Bakelite DP	Each	10	156.00	Rupees One Hundred Fifty Six Only
5 54/52	Supply and fixing of 230 volts 20/40 watts starter for fluorescent lamp. a) Group A	Each	150	20.00	Rupees Twenty Only
6 53/48	Supplying and fixing/replacing of flouresexcnt tube. a) 18 to 40 watts	Each	150	48.00	Rupees Forty Eight Only
7 46/19	Supplying of 65/80 watts heavy duty open construction Ferromagnetic copper ballast for fluorescent tubes.	Each	75	420.00	Rupees Four Hundred Twenty Only
8 47/21	Supply of Specital type lamps h) 36 Watts CFL P.34 I.No 4-38-19	Each	30	145.00	Rupees One Hundred Forty Five Only
11 51/36	Rewinding a...mm ceiling fan/after using necessary gauge annealed and insulated copper wire with necessary insulating, separators vibration arresting shellac, etc including replacement of bearings if any transportation to and from the spot to workshop inclusive of releasing the refixing. c) 1200MM P 109 Item 15.4	Each	30	630.00	Rupees Six Hundred Thirty Only
12 51/37	Releasing the existing fan dismantling testing painting after removing the existing painting by scraping and cleaning (Spray method) to less than 2 coats of approved make enamel paint to a ceiling fan and wiring and fixing of the same.	Each	50	278.00	Rupees Two Hundred Seventy Eight Only
13 52/44	Releasing the existing FTL Fitting all capacities, checking, testing and installing at same place. P.110 Item 16.5	Each	60	30.00	Rupees Thirty Only
15 54/62	Supplying and fixing Cordless calling bell suitable to operate on 230V 50 Hz AC/3V DC Supply, Cordless remote bell push with 2x1.5V DC Batteris and completely wired. a) Group A	Each	9	650.00	Rupees Six Hundred Fifty Only
5 84/9	Supplying & fixing relay for over load protection for window and split air conditioners.	Each	4	260.00	Rupees Two Hundred Sixty Only
3 83/7	Supply and fixing of condensing coil for Split Air Conditioners. c) 2 ton capacity	Each	8	4750.00	Rupees Four Thousand Seven Hundred Fifty Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri ADINARAYANA REDDY	
				Rate	Rate in Words
5 84/9	Supplying & fixing relay for over load protection for window and split air conditioners.	Each	8	300.00	Rupees three hundred only
3 83/7	Supply and fixing of condensing coil for Split Air Conditioners. c) 2 ton capacity	Each	10	810.00	Rupees eight hundred ten only
4 84/8	Supplying and fixing capacitor's (of approved make) for window/ split air conditioners b) 80 to 200 mfd Starting capacitor	Each	12	960.00	Rupees nine hundred sixty only
7 84/11	Supplying & filling refrigerent (F-22/F/12) for air conditioning equipments. Which includes the labour & Nitrogen gas for pressure and leak testing.	P/Kg	70	250.00	Rupees two hundred fifty only
8 84/13	Supplying and fixing electro mechanical/Pneumatic time switches including Vat.	Each	3	8000.00	Rupees eight thouand only

Rajesh.A
Signature of the contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.